

TESTING HP-3800 AT
STATE EMD CHECKING POINT
(LARPENTEUR & CLEVELAND)

Set up at BASE POINT

MHD READINGS

slope 200.239 .096
horiz. 200.230

slope 500.082 .080
horiz. 500.076

slope 1000.113 .097
horiz. 1000.107

slope 2000.456 .092
horiz. 2000.443

Check 100 ft. chain at
courthouse in the east
hall in the basement.
Tape left in courthouse
over night for room temp.

R.F.M. April 19, 1974 1
P. K. Sunny, Windy
Temp. 40°±

filter & single prism 200.335

filter & single prism 500.162

filter & single prism 1000.210

single prism 1000.210

filter & triple prism 1000.210

triple prism 2000.548

single prism 2000.568±
→ to jumpy in wind

fully supported 99.98

fully suspended 100.00