

SEC 5 T30N R22W

ANOKA CO.

Found granite monument in place at NW corner

" " " " " NW " "

" " " " " NE " "

For establishment of SW cor., and $\frac{W}{4}$ cor. see SEC 6 T30N

R22W.

In establishing SE cor. Sec. 5 by double proportionment.

Government witness trees gone. Measured EW between S $\frac{1}{4}$ cor.
Sec. 4 and SW cor. Sec. 6; and NS between NE cor. Sec. 17
and NE cor. Sec. 5. Set corner 22 Feb. 1950.

Established S $\frac{1}{4}$ cor. Sec. 5 by single proportionment between

SE cor. and SW cor. 22 Feb. 1950. Government witness tree
gone.

Established E $\frac{1}{4}$ cor. Sec. 5 by single proportionment between

NE cor. and SE cor. 23 Feb. 1950 Government witness trees
gone.

Established center of Sec. 5 by intersection 27 Feb. 1950.

Placed witness corner on EW $\frac{1}{4}$ line at its intersection with

E shore Deep Lake as shown on map 27 Feb. 1950.

Placed witness corner on W line Sec. 5 at its intersection

with shore of Deep Lake as shown on map 28 Feb. 1950.

NOTE: $\frac{W}{4}$ cor. Sec. 5 established on ice.

SEC 5 T30N R22W

