

(130)

XXVII XXIII XVII . XXI XX

	81		29
62			
	37		28
	37		27

M2

Return
Range

40.00

8000

68. Between Towns 28 & 29 N. M36
Range 23 West 4th Mer. Min. Terry

West between Sec. 14 & 36
Var. 11°-15'

40.00 Set post at gr Sec corner
E Br Oak 12 S. 72 W. 161
E Br Oak 11 N. 14 E. 216

3.00
40.00

50.00 Road from St. Paul to the
falls of St. Anthony bears N. 70 W

80.00

80.00 Set post at cor to Section
1. 2. 3 5 & 36

E Br Oak 12 N. 26 E. 5

E Br Oak 13 S. 4.5 E. 7

E Br Oak 13 S. 28 W. 6

Land high rolling
Soil i? rate - Timber
Br & Blk Oak

Oct 9th

v. M36
Min. Levy

Between Town. 28 & 29 N.
Range 23 West 4th Mer. Min. Levy

435
15'
mer
161
216
to the
ears N. 70 W
lectinis
20 E. 5
50 E. 4
27. 6

West between Sec. 24 & 35
Twp 11. 24'

- 3.00 Enter prairie
- 40.00 Set post at gr Sec corner
and made mound
80' 8 lks East.
- 80.00 Set post at corner to Sec.
2. 3. 34 & 35
and made mound
80' 8 lks South.

Land high rolling prairie
Soil L. rate.

Octo 7th

70. Between June 28 & 29 March M37
Range 23 West 4th Mer. Min. Levy

West between Sec. 34 & 34

Var 11° 24'

25.00	leave prairie center barrels	40.00
40.00	Set post at gr Sec corner	
	Br Oak 8 S. 5 E. 18	
	Br Oak 7 N. 28 E. 18	80.00
80.00	Set post at cor to Sec.	

3. 4. 33 & 34

Br Oak 24, N. 83 E. 45

Br Oak 13 N. 28 W. 40

B. Oak 18 S. 48 W. 89

First 30 chs brushy barrels
Sand high rolling Oak
Openings except 1st 30 chs

Oct 7th.

March M37
v. Min. Jerry

Between Run. 28 & 29 N. ^{71.}
Range 23 West 4th Mer. Min. Jerry

434
24'
barren
corner
E. 18
E. 18
Sec.

West between Sec 4 & 33
Var 11° 20'

40.00 Set post at gr Sec corner
E. 10 S. 3 E. 11.80
E no other near

80.00 Set post at corner to Sec.
4. 5. 32 & 33
E. 11 N. 86 E. 158
E no other near

3 E. 45
8 N. 40
8 N. 89

barren
Oak
rocks

Land high rolling
Soil 2? rate

Oct 7th

72. Between Towns 28 & 29 north
Range 23 West 4th Mer. Min. Terr. M38

West between Secs. 5 & 32
Var 11° 20'

38.00	Enter bottom	
40.00	Set post at gr Sec corner	
	E B. Ash 14 N. 20 E. 11	
	E W. Birch 12 S. 40 E. 35	
57.55	To the Mississippi river	
	Sack. Set meaner post.	
	E B. Oak 20 N. 68 E.	
	E No other near	

Sand high level
Soil 2^d rate

Oct 7th

M39

Township 29 North 75.

Between Ranges 22 & 23 N. 1/4 Mer. M. Sec.

Mer. Min. Sec.

74 12
15'

runs
post.
N. 20
E. 4

North between Sec. 31 & 36
Twp. 11 & 15'

- 28.50 Enter field
- 40.00 Set post at gr Sec corner
 Line 19 N. 68° E. 119
 Line 17 N. 69° W. 132
- 42.25 Leave field
- 75.00 Enter marsh
- 80.00 Set post at corner to Sec. 25, 30, 31 & 36
 Line 15 S. 75° E. 100
 Line 16 N. 80° E.

Broken Oak barrens intersper
sed with marshes

Oct 7th

Oct 8th

76. Township 29 North M40

Between Ranges 22 & 23 W. 4th mer. M. S.

North between Secs. 25 & 30

Var 10° 35'

- | | | |
|-------|---|-------|
| 2.00 | Leave marsh center Tank swp. | 40.00 |
| 30.00 | leave Tamarac swamp and enter oak barrens | |
| 40.00 | Set post at gr Sec corner
Pr Oak 13 N. 68 E. 29
E Pr Oak 14 N. 63 W. 151 | 80.00 |
| 80.00 | Set post at corner to Secs.
19. 24. 25 & 30
Pr Oak 7 N. 32 E. 20
E Pr Oak 12 N. 15 W. 175
E Pr Oak 11 S. 72 E. 50
Pr Oak 6 S. 76 W. 14 | |

Sand broken Oak barrens interspersed with marshes

Oct 8th

Township 29 North, 77.

Between Ranges 22 & 23 W. 4th Mer. M. S.

North between Sec. 19 & 24
Var 10° 45'

40.00 Set post for gr Sec corner
Br Oak 12 N. 45 W. 320
E no other near

80.00 Set post at cor to Sec.
13, 18, 19 & 24

- Br Oak 10 N. 86 E. 19
- Br Oak 6 N. 42 W. 32
- Br Oak 10 S. 36 E. 71
- Br Oak 8 S. 18 W. 31

Sand broken Oak barrens
interspersed with marshes

Oct 8th

78. Township 29 north M41.

Between Ranges 22 & 23 W. 4th mer Min. Serry

West between Sect. 13 & 18
Var. 11° 15'

40.00 Set post at gr Sec corner
Br Oak 7 S. 70 W. 62
B. Oak 8 N. 48 E. 74

80.00 Set post at corner to Sect.
7, 12, 13 & 18
Br Oak 12 N. 48 W. 74
Br Oak 13 S. 44 E. 8
Br Oak 10 S. 56 W. 21

Land high & rolling Oak
openings interspersed with
marshes.

Oct 8th

M41

Township 29 north

79.

Between Ranges 20 & 23 N. 4 to Mer. Min. S. 1/4

Mer. Min. S. 1/4

3418

North between Sec. 7 & 12
Var 11-15'

mer

40.00 Set post at gr sec corner
W. Oak 22 S. 22 E. 50
B. Oak 8 N. 12 E. 39

N. 62

E. 74

to Sec.

80.00 Set post at en to Section
1 E. 7 & 12

8 N. 74

E. 8

N. 21

Br Oak 9 N. 55 W. 6
Br Oak 8 N. 78 E. 93
W. Oak 7 S. 20 E. 59
B. Oak 10 S. 40 N. 27

Oak

with

Land high rolling oak
openings interspersed with
marshes

Set post

Set post

80. Township 29 north M42
Between Ranges 22 & 23 W. 4th Mer. N.S.

North between Sec. 1 & 6
Var 11° 15'

40.00 Set post at gr Sec corner
Pr Oak 11 S. 14 E. 33
Pr Oak 8 S. 32 W. 53

83.80 Intersect north boundary
and set a post for cor to
Town. 29 & 30 N. R. 22 & 23 W.
B. Oak 10 N. 24 E. 107
B. Oak 12 N. 18 W. 100
B. Oak 8 S. 42 W. 45
B. Oak 11 S. 32 E. 73

Land high rolling Oak
openings with marshes

Oct 8th

0 W. M53
Mini. Terry

4.6431

5.35'

lee corner

20 E. 16

27.33

100 lbs

six mile

corner

21422 W.

4.45

7.61

2. rate

lakes and

the water

I, James M. Marsh Deputy Surveyor do solemnly affirm that in pursuance of a Contract with Geo. W. Ames Surveyor General of the United States for Wisconsin & Iowa, bearing date the 23^d day of May 1847 & in strict conformity to the laws of the United States and the instructions of the said Surveyor General, I have regularly surveyed & established the foregoing township boundaries West of the fourth Principal Meridian Wisconsin Territory, and I do further solemnly affirm that the foregoing are the true and original field notes of the said survey executed as aforesaid

James M. Marsh
Deputy Surveyor

John Allen }
Mahlon Black } } Chairman
Michael ^{his} Peltier } } marked
^{mark} Nitrop Wm. R. Anderson
Sylv J. Smith

M 54

Subscribed by said James
M. Marsh Deputy Surveyor and
sworn before me at Stillwater St.
Croix Co. this 30th day of October 1847
J. B. Loney
Judge of Probate

Surveyor General's office
Dubuque Aug. 14, 1850

I certify that the foregoing is a
true copy of ^{a part of} so much of the original field
books containing the surveys executed by
James M. Marsh, Deputy Surveyor, under
his Contract of May 23^d 1847 - as contain
the surveys of that portion of his District
situated West of St. Croix Lake
in the Territory of Minnesota

C. H. Booth
Surveyor General

