

1291

64

52

7

23

28

53

9

16

37

44

XXV

XXIII

XXII

M2

M2

Survey of
Township Lines

Made by
Jesse T. Jarrett

Under Contract, Dated
May 30th 1853

M3

Names of Assistants.

Andrew F. Wiley }
George Webb } Chairmen.

John Hoyt } Sayerman

On
From
4th

Chairmen

31.09

38.9

Between Townships 28 & 29 North of Range
23 West of the 4th Principal Meridian

West Between Sections 5 & 32. Var. 11.° 2.0' East

Chains Commencing at Meander Corner
on Left Bank of Mississippi River
on line of Sections 5 & 32. Thence
Offset North 318 links; whence
Object on line on East side of Island
bears S. 63° W. Distance across 6.24
Chains. Therefore at

57.79 Set a post on East side of Island
for Meander Corner.

{ Maple S 15° W 150 links
No other near

60.49 To West side of Island & set
Meander Corner.

{ Ash S N 62 1/2° E 62 links
No other near & no large trees
on the Island.

From Meander corner on West side of
Island, Offset North 97 links whence
Object on line on Right Bank of River
bears S 79° W. Therefore at

Between Townships 28 & 29 of Range 23
West of the 4th Principal Meridian

Chains

65.53

Set a post for Meander corner
on the Right Bank of River.

1

{ Maple 10 N 71° W 65 links
Linden 12 S 35° W 53 links

70.00

To the Top of Bluff, bears S. E.

73.00

Enter Field, bears S 85° W

80.00

Set a post for the corner to
sections 5, 6, 31 & 32.

{ Bur Oak 15 N 6 1/2° E 308 links

Bur Oak 12 N 85° W 421 links.

No other near

Surface level after leaving Bluffs,
Bluffs steep. Soil 1st rate. Timber,
on Bluffs, Maple, Linden & Ash, on
upland scattering Bur Oak.

Between
23 West

Chains

10.82

40.00

70.00

76.14

9 of Range 23
Meridian

Between Townships 28 & 29 North of Range
23 West of the 4th Principal Meridian

Under Corner
of River.

Chains West between Sections 6 & 31.
Variation 10.58 East.

65 links

10.82 Leave Field, bears North & South.

53 links

40.00 Set a post for the 1/4 Section
Corner.

bears S. E.

{ Bur Oak 6 S 67° W 222 links

85° W

{ Bur Oak 8 S 82° W 463 links.

Corner to

70.00 Enter Prairie, bears N. W.

2.

6 1/2 E 308 links

76.14 Set a post in ground for the
Corner to Townships 28 & 29 North
of Ranges 23 & 24 West of the 4th
Principal Meridian.

2 1/2 W 421 links

Two pits, one 10 links North &
one 10 links South.

Leaving Bluffs

at rate, Timber,

3 Ash, etc

Bur Oak.

Surface level, Soil 1st rate.

Timber, Bur & Black Oak & Aspen.

Undergrowth Aspen & Hazel.

July 10th 1853

Township 29 North
Between Ranges 1238 24 West of the 4th Prim. Mer.

Chains North Between Sections 1836.

Variation 11° 26 East

40.00 Set a post for the $\frac{1}{4}$ Section
Corner.

{ White Oak 12 N 18 $\frac{1}{2}$ W 460 links
Black Oak 7 N 11° W 628 links

44.00 Leave Prairie N.W. & S.E.

80.00 Set a post for the corner
to Sections 25, 30, 31 & 36.

{ Bur Oak 12 N 20 $\frac{1}{2}$ W 354 links
Bur Oak 22 S 89° E 198 links.
Bur Oak 12 N 44 $\frac{1}{2}$ E 241 links.

No other near.

Surface level: Soil 1st rate,
Timber on 2nd $\frac{1}{2}$ scattering,
Undergrowth, Hazel, Bur &
Black Oak.

Township 29 North
Between Ranges 23 & 24 West of the 4th Prime Mer.

Chains North Between Sections 25 & 30.
Variation 10.38 East.

7.00 To the Top of Bluff of Mississippi
River, bears N. W. & S. E. 11

14.94 Intersect Right Bank of Mississippi
River & set Meander Corner. 11

4
Elm 6 S 55° W 218 links
Aspen 6 S 12° E 212 links

Offset West 340 links, whence
meander post on Left Bank of River
bears N 11° E Distance across
River 17.50 Chains

32.44 To Left Bank of River.

Surface level, except River Bluffs,
which are of gradual descent.
Timber, Elm, Aspen, Linden, Ash
& Oak. Undergrowth Willow,
Maple, Hazel & Oak.

July 18 1853

100
M52
Affidavit

I Jesse T. Jarrett Deputy
Surveyor, do solemnly swear
that in pursuance of a contract
with Warner Lewis Surveyor
General of the United States for
Wisconsin & Iowa, dated May the
30th 1853, and in strict conformity
to the laws of the United States
and the instructions of said
Surveyor General, I have regular-
ly surveyed and ~~subdivided~~ ~~into~~
~~Sections~~ established the follow-
ing Township Boundaries, Situ-
ated West of the 4th Principal Mer-
idian, in the ~~State~~ Territory of
Minnesota, viz: The South boundary
of Township 27 of Ranges 22, 23, 24, & lines
between Townships 27 & 28 of Ranges 22
& 24 lines between Townships 28 & 29
of Ranges 23 & 24, North boundary of

Townships 29 of Range 24 West of 4th Trin. Mer
lines between Ranges 22 & 23 Townships 27 & 28
lines between Ranges 23 & 24 and West boundary
of Range 24 of Townships 27, 28 & 29

And I do further solemnly swear that the
forgoing are the true and original field notes
of the said survey executed as
aforesaid.

Jesse Sanford

Deputy Sur

J. F. Wiley Chairman
Geo. Webb

John Shoart Assessor

Subscribed by said Jesse J
Sanford Deputy Sur, and sworn to
before me this at my office in the
City of Dubuque this 18th day
of Nov, 1853

Harmon Lewis
Sur. Genl.

