

# MONUMENT 132

## CERTIFICATE OF LOCATION OF GOVERNMENT CORNER

East Quarter Corner of Section 16, Township 30 North, Range 23 West, County of Ramsey, State of Minnesota.

At the corner location shown on the sketch

On September 13, 2010 found a cast iron monument, flush.

left monument as found       raised/lowered monument       removed monument (explain)

On \_\_\_\_\_ placed a \_\_\_\_\_

### SKETCH OF REFERENCE TIES



NAIL AND DISK  
IN 16 IN. OAK



N42°31'49"W  
172.81

AVENUE

NAIL AND DISK  
IN POWER POLE

N30°19'25"E  
86.50

INCINERATOR ROAD

PUNCH MARK  
ON CAP OF  
MONITORING  
WELL No. 03U014 MW

S34°04'23"W  
94.39

SNELLING

NAIL AND DISK  
IN POWER POLE

S30°12'24"E  
84.79

S16°59'13"W  
122.61

PUNCH MARK  
ON CAP OF  
MONITORING  
WELL No. 03L014 MW

RAMSEY COUNTY  
NAD83 (1986)

### MONUMENT 132

X= 555659.060 (Easting)  
Y= 207706.527 (Northing)

ALL DISTANCES ARE SHOWN IN U.S. SURVEY FEET.  
BEARINGS ARE FOR TIE REFERENCE PURPOSES ONLY.

Statements of evidence relative to this corner are on the following page.

I hereby certify that this document has been prepared by me or under my direct supervision this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Minnesota License No. \_\_\_\_\_

SIGNATURE

- County Surveyor       Deputy County Surveyor       Land Surveyor

OFFICE OF COUNTY SURVEYOR  
County of Ramsey

I hereby certify that this document was filed in the County Surveyor's office this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Michael D. Fiebiger, P.L.S.  
Ramsey County Surveyor

SIGNATURE

## MONUMENT 132

Found a 2 in. solid iron, down +/-10 in.; placed an 8 in. cast iron monument in cement, tied, August 26, 1991.

Retied monument, April 3, 2001.

Retied monument, March 9, 2005.

Retied monument, September 13, 2010.