



# MONUMENT 402

North Quarter Corner of Section 14, Township 29 North, Range 23 West

Set 1/4 Section post, Bur Oak 12 N43°E 68, Bur Oak 13 S89°W 73, November 3, 1847.

Found monument at 1/4 Corner between Sections 11 and 14, reset and tied it in May, 1897.

MN/Dot Right of Way Map No. 5-60 for T.H. 36 shows a stone monument at this location, date is not readable.

Found a cast iron monument flush and tied, July 23, 1974. (The origin of the cast iron monument has not been determined).

Checked monument, July 29, 1977.

Retied monument, August 10, 1999.

Removed old 20 in. cast iron monument; found a 2 in. iron, 1.8 ft. long, down 1.8 ft.; set a 20 in. cast iron monument down 18 in. and back filled, July 9, 2001.

Tied monument, July 11, 2006.

Retied cast iron monument within a cast iron manhole assembly, June 20, 2011.