

MONUMENT 405

Set post at Corner to Sections 7, 12, 13 and 18, Bur Oak 12 N48°W 74, Bur Oak 13 S44°E 8, Bur Oak 10 S56°W 21, October 8, 1847.

In establishing the Northeast Corner of Section 13, I found old Block Corner and also old lot stakes on the West side of Rice Street and from said stakes I fixed Section Corner and set monument; no witness trees, April, 1895.

Found a brass plug; dug down 3 ft. and found nothing; set a cast iron monument, July 9, 1976 (The origin of the brass plug has not been determined).

Checked monument, July 29, 1977.

Tied monument, June 7, 1990.

After construction by Mn/DOT, found monument with top missing; set P.K. nail, September 29, 1992.

Placed a short (4 5/8 in.) cast iron monument in concrete over broken cast iron monument, April 27, 1993.

Retied monument, July 19, 2002.

Retied monument, August 8, 2007.

Tied out monument for removal during road re-construction, May 24, 2010.

Monument loose, removed, February 17, 2011.

Set a 20 in. cast iron monument within a cast iron manhole assembly using construction ties; tied, September 14, 2011.