

MONUMENT 505

Northeast Corner of Section 27, Township 29 North, Range 22 West

Set post Corner to Sections 22, 23, 26, & 27, B. Oak 12 S73°E 19; Bur Oak 12 S64°W 1.23, November 29, 1847.

Found brass plug, removed and set a cast iron monument to grade in concrete; old granite monument 1 1/2 inches below cast iron monument, April 27, 1972 (City of St. Paul Notes).

Tied a cast iron monument, July 30, 1982 (City of St. Paul Notes).

Monument missing, re-established from ties in book 1329 C pg. 76; set P.K. nail, February 14, 1985 (City of St. Paul Notes).

Placed iron pin, March 12, 1987 (City of St. Paul Notes).

Found iron pin, dug down +/- 2 ft., probed down +/- 1 ft., found nothing; replaced iron pin with a 20 inch cast iron monument, December 6, 1995 (as shown on Certificate filed with the City of St. Paul signed by Richard Person December 28, 1995).

Retied cast iron monument, December 7, 1995 (as shown on Certificate filed with the City of St. Paul signed by Richard Person December 28, 1995).

Found and painted cast iron monument at grade for aerial target, March 22, 1996 (City of St. Paul Notes).

Tied cast iron monument for removal during road reconstruction, July 2, 2007.

Set a cast iron monument within a cast iron manhole assembly using construction ties, September 13, 2007.

Tied cast iron monument, September 17, 2007.

Checked condition of monument and ties, April 6, 2012.