



# MONUMENT 645

Northeast Corner of Section 11, Township 28 North, Range 22 West

Set post Corner to Sections 1, 2, 11, & 12, Black Oak 18 S52°E 194, Black Oak 16 N36°W 218, October 27, 1847.

Monument set by J.H. Armstrong, March, 1891. (City of St. Paul).

Placed ties on granite monument, February 8, 1934. (City of St. Paul notes).

Found a cast iron monument set by St. Paul, no date given in field book.

Tied monument for maintenance, May 18, 1998.

Removed cast iron monument for maintenance; found 1 1/2 in. iron down 2.3 ft. from road surface and 0.5 ft. south southwesterly; set 20 in. cast iron monument and cast iron manhole assembly at tie location, August 27, 1998.

Tied monument, July 21, 2006.

Retied cast iron monument, within a cast iron manhole assembly, June 6, 2011.