

East Quarter Corner, Section 8, T. 29 N. - R. 23 W.**Statement of Evidence**

- 1847 November 2nd, Isaac N Higbee, Deputy Surveyor United States Public Land Surveys indicates in his field notes that he "Set 1 / 4 Section Post"
One tie was recorded:
Bur Oak 12 inch diameter S 39 E 1.48 links
- 1896 August, Ramsey County Resurvey Noted Fixed 1/4 corner between Sections 8 and 9 from line of old fence running West. Government witness trees gone
- 1898 May 9th, Ramsey County Set Monument
- 1969 June 12th, Plat of ROSEDALE CENTER SECOND ADDITION shows a Cast Iron Monument at position.
- 1975 June 25th, Minnesota Highway Department set cast iron monument.
- 1977 July 15, Ramsey County field crew found cast iron and checked ties.
- 1980 Ramsey County field crew found cast iron top broken-off, base still in place.
- 1983 December 30th, Plat of FERRISWOOD shows a Ramsey County Cast Iron Monument at position.
- 1990 August 14th, Ramsey County crew removed broken cast iron; placed 20" C.I. and retied.
- 1997 October 23rd, Plat of GATEWAY BUSINESS PARK shows a Ramsey County Cast Iron Monument at position.
- 2022 April 13th, MnDOT survey personnel found a broken cast iron monument down 0.9 feet. Monument was pushed westerly of the road approximately 0.17' feet. The 3 tie positions are held for a computed NAD83(1996) Ramsey County Coordinate. Due to accessibility and safety reasons this monument will not be maintained anymore, and a witness will be set.

Summary and Conclusion:

This Certificate of Location is a perpetuation of the cast iron monument set on August 14th, 1990.