



## MONUMENT 296E

In establishing the 1/4 Corner between Sections 34 and 35. Measured the distance between the North East Corner and the South East Corner of Section 34 - 5277.20 and fixed the 1/4 Corner at 2638.60. Government Witness trees gone, August , 1896.

Found a manhole at Corner location, re-established monument based on local monumentation (see Survey Book # 2, pages 1, 2 and 4), 1974.

Set a 20 in. cast iron monument, 33.00 ft. east, on line, 1975.

Tied monument, April 29, 1988.

Monument destroyed by construction between 1988 and 1991, position re-established after traversing, 1992.

Placed a 20 in. cast iron monument and tied, August 25, 1993.

Retied monument, November 13, 1998.

Cemented monument, September 9, 1999.

Retied monument, August 29, 2006.

Retied cast iron monument, down +/-0.05 ft., August 19, 2011.