

MONUMENT 296N

In establishing the 1/4 Corner between Sections 34 and 35. Measured the distance between the North East Corner and the South East Corner of Section 34 - 5277.20 and fixed the 1/4 Corner at 2638.60. Government Witness trees gone, August, 1896.

Found a utility manhole at Corner location, re-established monument based on local monumentation (see Survey Book # 2, pages 1, 2 and 4), 1974.

Set a 20 in. cast iron monument, 33.00 ft. north, on line, 1975.

Tied monument, April 29, 1988.

Monument destroyed by construction between 1988 and 1991, position re-established after traversing, 1992.

Placed a 20 in. cast iron monument and tied, August 25, 1993.

Retied monument, November 13, 1998.

Cemented monument, September 9, 1999.

Retied monument, August 29, 2006.

Retied cast iron monument, flush, August 19, 2011.