

In Establishing the $\frac{1}{4}$ cor. between Sections 1 and 2 Government witness tree standing and found old oak stake and fixed $\frac{1}{4}$ cor and set monument Apr 10. 1895

Found Iron Monument at N.E. corner of Section 1 set by State Government witness trees gone tied it Sept 25 - 1897

Fixed Meander Corner No. 6 and set Monument Sept 22 1897

Fixed Meander Corner No. 5 and set Monument Sept 22 - 1897

The S.E. corner of Section 1 was fixed from stakes found in 3rd Add to N. St. Paul and Castle Found two Gov. witness trees, found old stake at Section corner OK for corner tied it and set monument Sept 22 - 1897

In Establishing the $\frac{1}{4}$ Corner on the North of Section 1 found one old Government witness stump Set monument July 20 1898

In Establishing the North West corner of Section 1 Run straight line from corner to corner East and West and fixed Section Corner $\frac{1}{2}$ way Set monument July 20 1898

The $\frac{1}{4}$ corner between Sections 1 and 12 was fixed from stakes found in the 4th add to N. St. Paul and Castle Government witness trees gone Set Mont. Dec. 1899 Dec 28 - 1898

In Establishing the South West corner of Section 1 Found two Government trees Set Mont. Dec 1899 Dec 27 1898

Fixed the Centre of Section 1 by Intersection and set Mont Oct. 18 - 1900.

13
2893
2894
2895
2896
2897
2898
2899
2900