



77.34° @
57.30° @
70.84° @

FP 30.21
FP 16.88
30.72 TP
27.78° @ 8"
5.5° @ 5"
12" @ 0

66° 7.41 MC N° 7
08° 8.48
35.69
770
B.T.

10° @
1535 MC N° 6
03° 32.3
29.5 @ 3"

29.79 @ TP
10.5 post
60.60 TP

LAKE OWASSO

Nail in Otrea
S21°30'E Mag.

bush 20.86
3.74 bush

2636.40
1318.20
ALEXINGTON AVE
08° 58.76
33.76
43.47° @ 4"
42.17° @ 6"

2609.33

ST. PAUL & DULUTH RAILWAY

DALL ST
2582.26
2571.37

BENNETT LAKE

FP 38.69
FP 46.15

07° 29.52
62.13° @ 8"

Tree 38.10

1319.50
2639
13.50 - brush

SNED

In Establishing the N.W. Corner of Sec 2 on Town line between Rose and Mound View I found Old Oak Hub and also part of old witness tree and set Monument May 1896

In Establishing the S.W. Corner of Sec 2 found old Iron Stake
No witness trees set Monument in May 1896

The $\frac{1}{4}$ Corner between Sections 2 and 3 was fixed by J. W. Armstrong in Dec. 1896
Set Monument May - 1897

The $\frac{1}{4}$ Corner between Section 2 Town 29 R 23 and Section 35 Town 30 Range 23 was fixed by J. W. Armstrong in Dec - 1896 set Monument Aug 9 - 1897

Meander Corner No. 6 was fixed by Armstrong set Monument Aug 9 1897

Meander Corner No. 7 was fixed by Armstrong set Monument Aug 9 - 1897

The Center of Section 2 was fixed by Armstrong in Dec - 1896 Set Monument Nov 10 - 1897

The $\frac{1}{4}$ Cor. on South of Sec. 2 fixed by running straight from Cor. to Cor. and taking $\frac{1}{2}$ the distance.
Set Monument in Marsh Nov. 10 - 1897

The $\frac{1}{4}$ Cor. on East of Sec. 2 fixed by Armstrong Dec 1896 Armstrong measured the distance North from $\frac{1}{4}$ Corner East of Sec 11 to Lake 2nd prarated Set Monument Nov 10 - 1897

The South East Cor. of Sec. 2 was Established by local evidence. Three men who were familiar with the location of the original stake verified the present Mont. They were John McCaron Thomas Brennan and William Gould Sr. Each one said that the Mont. was placed where the original stake stood and further Mr. Gould said the present traveled road was placed on the section line for about 1300 feet going West. There were present when the Cor. was fixed Gates A Johnson Jr County Surveyor Gates A Johnson Deputy Surveyor Edward A Schaffer & Thomas Gould, Chainmen Dated May 21st 1895

The North East Corner of Section 2 was fixed Jan 11 - 1898 in Lake Owasso.