



Iron
 0.30
 Boulder Mont @ 29.40.06
 0.08 S of line
 Center GILBERT AVE Iron
 N.E. Cor. Shady Side

Found Iron Monument set by State at N.E. corner of Section 1 and one Government stump
tied it Oct 11 - 1897

Set monument at $\frac{1}{4}$ corner Oct - 1897

The $\frac{1}{4}$ corner on E side of Section 1 on county line comes in swamp found old stake
no Government witness trees nothing to tie to Oct 9 - 1897

Set monument at $\frac{1}{4}$ corner Oct 1897

The S.E. corner of Section 1 comes near edge of swamp Found one Government stump.
nothing to tie to Oct 8 1897 Set Monument Oct - 1897

The $\frac{1}{4}$ corner between Sections 1 and 12 Found one Government tree standing and stake set by Fitz
tied it Oct 5 - 1897 Set monument Nov 15 - 1901

In Establishing Meander corner No 9 Ran a line N from $\frac{1}{4}$ corner between Sections 1 and 12
using stakes found in Shady side Add. Government distance and fixed Meander corner No. 9
no Gov. witness trees Set Mont. ⁽²⁵⁾ 55 E of Meander corner Feb 23 - 1902

The Northwest cor. Sec. 1 Two government trees found by Fitz Jan 1901 Mont set March 1901

The $\frac{1}{4}$ $\frac{1}{4}$ cor on West side Sec. 1 Established by Fitz Jan. 1901 Mont. set March 1901

The $\frac{1}{4}$ corner on West side Sec. 1 Established by Fitz Jan 1901 Set Mont. Nov. 14 - 1901

In Establishing Meander corner No 8 Ran a straight line from $\frac{1}{4}$ corner between Sec 1 and 2
to Section corner 1. 2. 12 and 13 pro-rated and fixed Meander corner No 8
no Government trees Jan 24 - 1902

In Establishing the $\frac{1}{4}$ cor. on the N. of Section 1 Ran straight line E and N and pro-rated
Jan 1903 Set mont. Dec. 22 - 03

Fixed the centre of Section 1 by Intersection Jan 1903 set Mont Dec. 22 - 03