

1330.8  
90.13  
2679.11

1334



The North East Corner Sec. 2 Two government trees found by Fitz Jan 1901 Set mont. Mch 1901

Meander Cor No. 7 N side Sec. 2 East shore Bald Eagle one govt tree found by Fitz Jan 1901  
Set mont. June 1901

$\frac{1}{4}$   $\frac{1}{4}$  Cor East side N.E.  $\frac{1}{4}$  Sec 2 Established by Fitz Jan. 1901 Set mont. Mch 1901

Cor on East side Sec. 2 Established by Fitz Jan. 1901 Set mont. Nov. 14 - 1901  
2 Govt stumps

In Establishing Meander Corner No 8 Ran a straight line from  $\frac{1}{4}$  corner between Sections 1 and 2  
to Section Corner 1. 2. 12 and 13 prorated and fixed Meander Cor No. 8  
no Government witness trees Jan. 24 - 1902

In Establishing Meander Corner No 14 Ran a straight line from Meander Corner No 7  
to N.W. corner Section 2 and fixed Meander Corner No 14 Government distance  
E from N.W. corner Section 2 No Government trees Feb. 4 - 1902 Set Mont. Dec. 13 - 1902

In Establishing the N.W. corner of Section 2 found one Government witness stump  
and fixed Section corner Jan 30 - 1902 Set Mont. Dec 13 - 1902

In Establishing Meander Corner No 13 found one Government witness tree  
and fixed Meander Corner No. 13 Jan 31 - 1902 Set. Mont. Dec. 13 - 1902

$\frac{1}{4}$  corner on the N. of Sec 2 in Lake

$\frac{1}{4}$  corner between Sections 2 and 3 in Lake

$\frac{1}{4}$  corner between Sections 2 and 11 in Lake

The S.W. corner Sec. 2 in Lake

The S.E. corner Sec. 2 in Lake