



2092 6
2672 6
2385.2

The North West corner of Section 13 was fixed from stakes found in White Bear
Old Government trees were standing when White Bear was surveyed April 14 - 1899
Set Mont. Nov. 28 - 1901

Meander corner No. 2. was fixed from stakes found in White Bear April 14 - 1899
Set Mont. Nov. 28 - 1901

In Establishing Meander corner No. 3 Produced the line straight South from the
two Government corners and fixed Meander corner No Gov. witness trees
Set Mont. Nov. 30 - 1901

In Establishing Meander corners No. 39 and 40 Measured E. from S. W. corner
of Section 13 Government distance and fixed corners No Government trees Jan 21 - 1902

Fixed the centre of Section 13 by Intersection Jan. 22 - 1902
Set Mont. on 1/4 line 1146.50 N. of centre Dec. 5 - 1902

In Establishing the 1/4 corner between Sections 13 and 14 produced line East
using Mont. at centre and Iron Mont. at 1/4 1/4 corner No Gov. trees
Set Mont. Dec. 5 - 1902