



3 nails in oak F. Post.  
41.13  
73.26  
3 nails in oak F. Post.

New tree taken 9/26/21

350.3' from west rail on road to Mont.

2640.

3 nails in oak  
12 nails in oak

Guard Rail

Guard Rail  
10" 80

3 Nails in F.P.

78.15 B.O. 6"  
69.33 B.O. 8"  
78.51 B.O. 24"

New tree taken 9/14/10

MINNEAPOLIS ST. PAUL & SOUTHERN STE. MARIE

2628.30

Gov. tree  
70.24°  
62.70  
1514  
41.51  
108.43

20  
101.54

BASSWOOD LAKE

LAMBERT LAKE

1346.20

2639.60  
12.55°  
MCN° 21

0.1293  
0.1615  
900

MCN° 20

67.15° Tree

Tree

Tree 1507

Tree 36.10

2628.87

1200

1668° 21.24°  
Tree Tree

Tree 72.67

1245.10

1383.77

2628.87

1293.40

2625.60

38.55° Tree

73.42° Tree

1089

3016"  
103.10  
3016"  
80.92

Tree 21.33  
560  
Tree 20.21

8" Drive  
92.85  
F.P. 5479

In Establishing Meander Corner No. 20 found both Government witness trees standing  
fixed corner and tied it May - 1896 Set Mont Dec. 11 - 1899

In Establishing the South West Corner of Section 20 Measured North from  $\frac{1}{4}$  corner  
between Section 29 and 30 - 2636.50 which checked the line of fence running East  
Government witness trees gone Fixed corner tied it and set Monument May 1896

In Establishing the  $\frac{1}{4}$  corner between Sections 19 and 20 Found both Government witness trees  
standing Fixed corner on fence post in small marsh May. 11 - 1896  
Set Mont Dec. 11 - 1899

In Establishing the North East Corner of Section 20 found old stake 33ft North of  
Section corner on line of old fence Government witness trees gone  
Fixed corner and tied it November 19 - 1897 Set Mont May. 11 - 1898

In Establishing the  $\frac{1}{4}$  corner between Sections 17 and 20 found Government witness tree  
Fixed corner and tied it March 1898 Set Mont May. 11. 1898

In Establishing the North West Corner of Section 20 Prorated and fixed  
Section corner half way Government witness trees gone March 1898  
Set Mont May. 11. 1898

In Establishing the  $\frac{1}{4}$  corner between Sections 20 and 21 Found old Government  
witness tree and an old stake at  $\frac{1}{4}$  corner. Set Monument Aug. 18. - 1898

In Establishing the S.E. corner of Section 20 Ran straight line from Government corner North and  
South Prorated and fixed Section corner in Lambert Lake Jan. 1900

In Establishing Meander Corner No. 21 Ran straight line prorated and fixed Meander  
corner. Government witness trees gone. Jan. 1900 Set Mont. May 3. 1900

In Establishing the  $\frac{1}{4}$  corner between Sections 20 and 29 Ran straight line East and West  
Prorated and fixed  $\frac{1}{4}$  corner in Lambert Lake Jan. 1900

Fixed the centre of Section 20 by Intersection Jan 1900