



For $\frac{1}{4}$ corner between Sections 25 and 26 - see Sec. 25

Aug 28 - 1896

In Establishing the N.W. corner of Section 26 Ran East from $\frac{1}{4}$ corner between Sections 25 and 27
Government distance No Government trees Feb. 1900 Set Mont.

Found old original stake at $\frac{1}{4}$ corner between Sections 25 and 26 Government witness trees gone
Retied it and set Monument Aug 29 - 1896

In Establishing the $\frac{1}{4}$ corner between Sections 26 and 27 Ran straight line North
and South and fixed $\frac{1}{4}$ corner No Government witness trees
Set Mont. 1899

In Establishing the South West corner of Section 26 found old Boulder Monument 33 ft North
from Section corner Fixed Section corner and set Monument Government witness trees gone
Found old hub at Section corner Aug. 1896

In Establishing the $\frac{1}{4}$ corner between Sections 26 and 35 found two Boulder Monuments
one at the N.W. corner and one at the N.E. corner of White Bear Road & Wildwood Road
and also found old stake at $\frac{1}{4}$ corner which check the two Boulder Monuments
Government witness trees gone set Monument at $\frac{1}{4}$ corner and tied it Aug. 1896

Fixed center of Section 26 by Intersection tied it and set Monument Aug - 1896

In Establishing the South East corner of Section 26 Found old stake 33 ft N. of fence
Set Monument July. 20. 1898

In Establishing the N.E. corner of Section 26
Set Mont. July. 20. 1898