



LAMBERT LAKE

LAMBERT ISLAND

29

2628.87

2628.87

2622.16

2624.33

1303.43

2619.73

M.C. No. 23

tree 81.16

tree 58.15

14.96

tree

tree 6" 25.10

90°30'

tree 18.77

1308.65

2619.80

post 49.47

tree 67.87 2617.30

tree 172.25

tree 116.83

tree 56.55 stake

tree 72.67

2636.50

2639.60

tree 56.85

tree 36.30

1308.30

1022.86

tree 2616.60

tree 42.10

1308.30

2639.60

Boulder 104.5

tree 12" 48.25

1318.74

1318.74

2637.48

1616.74

tree 59.85

tree 59.18

tree 39.38

89°53'

90°12'

F.P.

34.23

In Establishing Meander Corner No. 20 found both Government witness trees standing,
fixed corner and Retied it May 1896 Set Mont Dec. 11 - 1899

In Establishing the North West Corner of Section 29 Measured North from $\frac{1}{4}$ corner
found between Sections 29 and 30 - 2636.50 which checked the line of fence running
East Government witness trees gone, fixed corner tied it and set Monument May 1896

In Establishing the $\frac{1}{4}$ corner between Sections 29 and 30, found Iron stake at $\frac{1}{4}$ corner
Government witness trees gone Retied it and set Monument 1895

In Establishing the South West Corner of Section 29 Found old Iron stake
Government witness trees gone, tied it and set Monument Aug 1895

In Establishing the $\frac{1}{4}$ corner between Section 29 and 32 found old original stake
Government witness trees gone Retied it and set Monument 1895

In Establishing the South East Corner of Section 29 Measured East from $\frac{1}{4}$ Section corner
between Sections 29 and 32 - 2619.80 which checked the line of fence running South
Government witness trees gone Retied corner and set Monument. 1895

In Establishing the $\frac{1}{4}$ corner between Sections 20 and 29 Ran straight line East and West
Prorated and fixed $\frac{1}{4}$ corner in Lambert Lake Jan. 1900

In Establishing the N.E. corner of Section 29 Ran straight line North and South from
Government Corners. Prorated and fixed Section corner in Lambert Lake Jan. 1900

In Establishing the $\frac{1}{4}$ corner between Sections 28 and 29 Ran straight line North and South
Prorated and fixed $\frac{1}{4}$ corner in Lambert Lake Jan. 1900

In Establishing Meander Corner No. 23 Ran straight line North and South
Prorated and fixed Meander Corner Jan 1900 Set Mont. May 3 - 1900

Fixed the center of Section 29 by Intersection Jan. 1900 Set Mont. Apr. 1900