





nothing to tie to  
Meander No. 26

Meander No. 27

Otse  
53.77  
41.07  
30

Meander No. 28

Meander No. 31

40  
1271  
1920  
1/6  
Otse  
Otse

In Establishing the North West corner of Section 30 found Iron stakes at Block corners in Vadnais Park Addition and fixed corner and set Monument Apr 1895

In Establishing the  $\frac{1}{4}$  corner between Sections 19 and 30 Ran straight line Prorated and fixed corner Retied it No Government trees Apr. 28, 1896 Set Mont. May 11 - '98

In Establishing the  $\frac{1}{4}$  corner between Section 30 P 30 R 22 and Sec. 25 T 30 R 23 fixed  $\frac{1}{4}$  corner from stakes found in Vadnais Park on Rice St. Retied it and set Monument June 1896.

In Establishing the South West corner of Section 30 Ran straight line and Prorated and fixed Section corner No Gov't trees Set Monument July 1896

In Establishing the  $\frac{1}{4}$  corner between Sections 29 and 30 Found Iron stake at  $\frac{1}{4}$  corner Government witness trees gone Retied it and set Monument 1895

In Establishing the South East corner of Section 30 Found Iron stake Aug. 1895 Government witness trees gone Set Monument.

In Establishing the North East corner of Section 30 Measured North from  $\frac{1}{4}$  corner, found between Sections 29 and 30 - 2636.50 which checked the line of fence running East Gov't witness trees gone Fixed corner, tied it and set Monument May 1896

In Establishing the  $\frac{1}{4}$  corner between Sections 30 and 31 Same as Meander Corner No. 27 Ran straight line East and West Prorated and fixed  $\frac{1}{4}$  corner No Government trees Set Mont. Apr. 1900 Dec. 1899

In Establishing Meandered corners No. 26-28-31 Ran straight line East and West Prorated and fixed Meandered corners No Gov't trees Dec. 1899 Set Monts. Apr. 1900