



In Establishing the $\frac{1}{4}$ corner between Sections 27 and 34 Measured West from North East corner of Section 34 - 2640.52 which checked the line of fence running North Government witness trees gone, fixed corner tied it and set Monument Aug-1896

In Establishing the North East corner of Section 34 found old Boulder Monument on North side of Road 33 ft North from Section corner found old stake at Section corner Government witness trees gone tied it and set Monument Aug 1896

In Establishing the $\frac{1}{4}$ corner between Sections 34 and 35 Measured the distance between the North East corner and the South East corner of Section 34 - 5277.20 and fixed $\frac{1}{4}$ corner at - 2638.60 Gov't witness trees gone Aug-1896

In Establishing the South East corner of Section 34 found one Government witness stump fixed corner and set Monument Aug-1896

In Establishing the South West corner of Section 34 Found old ties Government witness trees gone July-18-1898 Set Monument Aug 16-1898

In Establishing the $\frac{1}{4}$ corner on the South of Section 34 Found old stake at $\frac{1}{4}$ corner and also found Iron stake in Darle Park Government witness trees gone July-18-1898 Set Monument Aug 16, 1898

In Establishing the North West corner of Section 34 found Government witness stump and an old stake at Sec. corner. Set Monument Aug. 16. 1898

In Establishing the $\frac{1}{4}$ Corner between Sections 33 & 34, Ran straight line from corner to corner and fixed $\frac{1}{4}$ corner $\frac{1}{2}$ way Gov't trees gone Feb. 21 - 1900 Set Mont July, 1900

Fixed the centre of Section 34 by Intersection and set Monument July 1900