



Iron  
 0.30  
 Boulder Mont @ 29.40.06  
 0.08 S of line  
 Center GILBERT AVE Iron  
 N.E. Cor. Shady Side

Found Iron Monument set by State at N.E. corner of Section 1 and one Government stump tied it Oct 11 - 1897

Set monument at  $\frac{1}{4}$  corner Oct - 1897

The  $\frac{1}{4}$  corner on E side of Section 1 on county line comes in swamp found old stake no Government witness trees nothing to tie to Oct 9 - 1897

Set monument at  $\frac{1}{4}$  corner Oct 1897

The S.E. corner of Section 1 comes near edge of swamp Found one Government stump nothing to tie to Oct 8 1897 Set Monument Oct - 1897

The  $\frac{1}{4}$  corner between Sections 1 and 12 Found one Government tree standing and stake set by Fitz tied it Oct 5 - 1897 Set monument Nov 15 - 1901

In Establishing Meander corner No 9 Ran a line N from  $\frac{1}{4}$  corner between Sections 1 and 12 using stakes found in Shady side Add. Government distance and fixed Meander corner No. 9 no Gov. witness trees Set Mont. <sup>(25)</sup> 55 E of Meander corner Feb 23 - 1902

The Northwest cor. Sec. 1 Two government trees found by Fitz Jan 1901 Mont set March 1901

The  $\frac{1}{4}$   $\frac{1}{4}$  cor on West side Sec. 1 Established by Fitz Jan. 1901 Mont. set March 1901

The  $\frac{1}{4}$  corner on West side Sec. 1 Established by Fitz Jan 1901 Set Mont. Nov. 14 - 1901

In Establishing Meander corner No 8 Ran a straight line from  $\frac{1}{4}$  corner between Sec 1 and 2 to Section corner 1. 2. 12 and 13 pro-rated and fixed Meander corner No 8 - no Government trees Jan 24 - 1902

In Establishing the  $\frac{1}{4}$  cor. on the N. of Section 1 Ran straight line E and N and pro-rated Jan 1903 Set mont. Dec. 22 - 03

Fixed the centre of Section 1 by Intersection Jan 1903 set Mont Dec 22 - 03