



In Establishing the N.W. Corner of Section 6 found Stone Monument marked T30R24 51
at corner of fences no Gov. ties Jan 7-1903

In Establishing the $\frac{1}{4}$ Corner on the N of Section 6 run straight line E and W and
fixed $\frac{1}{4}$ corner Gov. distance from NW cor. Sec 6 Jan 22-1903 and set Monument.

In Establishing the N.E. corner of Section 6 run straight line E and W and fixed
Section corner Gov. distance from N.W. cor. Sec. 6. Jan 20-1903 and set Monument

In Establishing the $\frac{1}{4}$ corner between Sections 5 and 6 prorated N and S and
fixed $\frac{1}{4}$ corner no Gov. ties Jan 20-1903 - and set Monument

In Establishing the $\frac{1}{4}$ corner on the W of Section 6 found two Government trees
Jan 25-1903 and set Monument.

In Establishing the S.W. corner of Section 6 prorated N and S and fixed
Section corner in Lake. Jan 23-1903 and set 3 Monuments on shore of Lake.

In Establishing the $\frac{1}{4}$ corner between Sections 6 and 7 run straight line E and W
and fixed Section corner Gov. distance found 1 Gov. stump Jan 6-1903 and set Monument.

In Establishing the N.E. corner of Section 6 prorated N and S and fixed
Section corner no Gov. ties Jan 21-1903 and set Monument.

Fixed the center Section 6 by Intersection Jan 23-1903 and set Monument.