





In Establishing the S.E. Corner of Section 7 Found old stake at Section Corner and also found old stakes in Iron Works Plat no Gov. witnesses trees May 15-1901  
Set Mont. June 1-1901

In Establishing the  $\frac{1}{4}$  Corner between Sections 7 and 18 Found old stake at  $\frac{1}{4}$  Corner and also found stakes in Shields Add. to Iron Works Plat Gov. witnesses trees given  
Set Mont. June 1-1901 May 21-1901

In Establishing the  $\frac{1}{4}$  Corner on the W of Section 7 Found one Government tree and one Government tree stump fixed Corner May 28-1901  
Set Mont. June 15-1901

In Establishing the S.W. Corner of Section 7 Found two Government trees and one Government tree stump fixed Corner May 27-1901  
Set Mont. June 15-1901

In Establishing the N.W. Corner of Section 7 prorated N and S and fixed Section Corner in Lake Jan 23-1903 and set 3 Monts. on shore of Lake

In Establishing the  $\frac{1}{4}$  Corner between Sections 6 and 7 run straight line E and W and fixed Section corner Government distance found one Gov. stump Jan. 6-1903 and set Mont.

In Establishing the N.E. Corner of Section 7 prorated N and S and fixed Section corner no Gov. trees Jan 21-1903 and set Mont.

In Establishing the  $\frac{1}{4}$  Corner between Sections 7 and 8 found one Gov. tree Jan. 5-1903 and set Mont.

Fixed the Center of Section 7 by Intersection Jan 24 1903 and set Mont.