

In Establishing the South East corner of Section 9 Found our old Government witness
stump fixed corner and tied it in May 17-1896
Set Monument Oct. 28-1897

In Establishing the North East corner of Section 9 found both Government witness stumps
fixed corner and tied it March 17-1898
Set Monument July 11-1898

In Establishing the $\frac{1}{4}$ corner between Sections 9 and 10 Run straight line from corner to
corner and fixed $\frac{1}{4}$ corner $\frac{1}{2}$ way Government witness trees gone June 11-1898

In Establishing the $\frac{1}{4}$ corner between Sections 9 and 16 Run straight line from corner
to corner and fixed $\frac{1}{4}$ corner $\frac{1}{2}$ way Government witness trees gone May 28-1898
Set Monument July 11-1898

In Establishing the South West corner of Section 9
May 26-1898
Set Monument June 18-1898

In Establishing the $\frac{1}{4}$ corner between Sections 8 and 9 Found our Government witness
stump and an old stake May 26-1898
Set Monument June 18-1898

In Establishing the $\frac{1}{4}$ corner between Sections 4 and 9 Run straight line
from corner to corner and fixed $\frac{1}{4}$ corner $\frac{1}{2}$ way June 16-1898
Government witness trees gone
Set Monument July 11-1898

In Establishing the North West corner of Section 9 This corner was fixed by
running North and South between $\frac{1}{4}$ corners and fixed Section corner $\frac{1}{2}$ way
Government witness trees gone Found old stake June 15-1898
Set Mont. June 18-1898

Established the center of Section 9 by Intersection May 4-1901
and set Mont.