



The N.E. Corner of Section 18 was fixed from stakes found in Lake view Add to Minneapolis Stock Yards
Gov. witness trees gone
Set Mont. Nov. 1899

In Establishing the N.E. Corner of Section 18 Found old stake at Section Corner
and also found old stakes in Iron Works Plat no Gov. witness trees May 15-1901
Set Mont. June 1-1901

In Establishing the $\frac{1}{4}$ Corner between Sections 7 and 18 Found old stake at $\frac{1}{4}$ Corner
and also found stakes in Shields Add. to Iron Works Plat. Gov. witness trees gone
Set Mont. June 1-1901 May 21-1901

In Establishing the N.W. Corner of Section 18 Found two Gov. witness trees and one
Gov. witness tree stump fixed Corner May 27-1901
Set Mont. June 15-1901

In Establishing the $\frac{1}{4}$ Corner on the W of Section 18 Found two Gov. witness tree stumps
and also found Iron at $\frac{1}{4}$ Corner
May 31-1901
Set Mont. June 22-1901

In Establishing the S.W. Corner of Section 18 Found old stake near corner of fence
no Gov. witness trees
June 7-1901
Set Mont. June 30-1901

In Establishing the $\frac{1}{4}$ Corner between Sections 18 and 19 Found stake at $\frac{1}{4}$ $\frac{1}{4}$ Corner and
also found stakes in West End Add to Minneapolis Stock Yards produced the line N to
 $\frac{1}{4}$ Corner and Established $\frac{1}{4}$ Corner found one Gov. witness tree stump June 4-1901
Set Mont. June 22-1901

In Establishing the $\frac{1}{4}$ Corner between Sections 17 and 18 Ran straight line from Corner to Corner
and fixed $\frac{1}{4}$ Corner half way no Gov. witness trees
Aug. 6-1901
Set Mont. Aug. 17-1901

Fixed the Center of Section 18 by Intersection Jan 28-1893 and set Mont.