





For North West Cor. of Section 25 See Sec. 26 Set Mont. Aug. 3-1897

In Establishing the North East Cor. of Section 25 This Cor. was fixed from  
iron stakes found at Block corners and also found old stake at Section Cor.  
Fixed Cor. tied it and set Mont. Apr. 1895- no Gov. ties

In Establishing the  $\frac{1}{4}$  Cor. between Sec 25 T30 R. 23 and Section 30 T30 R. 22.  
This Cor. was fixed from Sub. Div. stakes found along the East side of Rice St.  
Gov. witnesses trees gone Fixed Cor. tied it and set Mont. June 1896

In Establishing the South East Cor. of Section 25  
Set Mont. July 1896

The South West corner of Section was fixed in July 29-1897 set Mont.

The  $\frac{1}{4}$  Cor. between Section 25 and 36 was fixed in July 30-1897 set Mont.

The  $\frac{1}{4}$  corner between Sections 25 and 26 was fixed from old stake found. no Gov. ties  
Fixed Cor. tied it and set Mont. July 28-1897 set Mont. Aug. 3-'97

In Establishing the  $\frac{1}{4}$  Cor. between Sections 24 and 25 Run straight line from Cor.  
to Cor. and fixed  $\frac{1}{4}$  Cor.  $\frac{1}{2}$  way Gov. trees gone Jan 21-1899  
Set Mont. Nov. 1899

Fixed the Center of Section 25 by Intersection and set Mont.  
Jan 24-1899