

## PLACE IN SECTION CORNER

NHD 21235

FILESPHONE MESSAGE

T30N

34

35

R22W

T29N

3

2

Received by DAVE PEARSON, R.L.S. Date APRIL 28, 1981~~Mr.~~ ~~You were called at~~ 8:45A.M.

P.M.

~~Mr.~~ CALLED RON MEYER, R.L.S.of RAMSEY COUNTY Phone 484-9104 Ext. \_\_\_\_\_The Message was THE SOUTHEAST CORNER OF SEC. 34, T30N, R22W

ON Co. Rd. "D" west of White Bear Ave. may be set at an incorrect location. The old county section maps for Sec. 34 & 35 show distances from the S<sup>1</sup>/<sub>4</sub> of 34 to the SE of 34 as 2644.0' [EDM 2639.34 (-4.66')] and SE of 34 to the S<sup>1</sup>/<sub>4</sub> of 35 as 2633.42' [EDM 2637.80 (+4.38')]. This indicates that if the SE Cor. of Sec. 34 were moved about 4.5 ft east these old dimensions would be ~~very~~ very close. Also, the E<sup>1</sup>/<sub>4</sub> Corner of Sec. 34 was set "lost" and by holding the NE Corner & E<sup>1</sup>/<sub>4</sub> Corner of Sec. 34 and pushing it south causes the corner to fall 6.65 ft east of the present corner. I feel this corner position merits further investigation before accepting its present position.

Destroy \_\_\_\_\_

File