

N.W. COR. SEC. 6-30-22
MONU. NO. 135P (13SC)

Found $\frac{3}{4}$ " iron in concrete. Dug down
1.2 ft. and found 2" sq. iron with
flange down. 3.5 ± 1 ft. Aug. 27, 1974.

Placed cast iron manv. Aug. 28, 1974.
over 2" sq. iron with cement to
steady cast. at base.

Retied Oct. 25, 1974

PLACED $\frac{4}{2}$ CAST IRON MONT. 2" SQ.
IRON DOWN 1.15 FT. 28-JUNE-85

Tied monu. for const. removal. 4-1990.

Removed. short C.I. 5-31-90.

Placed short cast iron ($\frac{4}{8}$ " in
quick-set 45 cement and rock. 10-30-90

Retied monu. 1-27-93

Set 20" C.I. marked "3RD CORR. LINE"

0.75 ft. S. of closing corner

(orig. granite monu.). 7-26-95

Maint. Dept filled 1.2 ft. summer 1998.

Maint. Dept. set 27" MH assembly over
monu's. (down 1.2') in old pavement. 7-25-02

TIED OUT MONU. "135C" 07-03-07

135P
AKA (13SC)

Closing Cor. ties

