

N.W. COR. SECTION 5, T29, R22  
MONU. NO. 315

Found granite monu. 1975.  
Granite monu. down 0.3' and 1± ft. west  
of sign and post. Retied. 3-5-93  
Monument not found due to MN DOT road  
reconstruction. Dug down ± 2.5 ft. and  
probed down ± 4.0 ft; found nothing 8-3-11  
Re-established position using remaining ties  
and adjacent section monumentation. Set  
a 20 in. C.I.M. flush in grass, tied and  
placed a Ramsey County Surveyor sign  
and post 2.5 ft N. of monument 7-19-12.

Checked:

