

N 1/4 CORNER SEC. 10-29-22

MONU. NO. 366

Found MH. at intersection. Used P.K.'s placed by Mr. Don Campbell and used by State Hwy. Dept. in measuring sections 1-4, for Maplewood. Placed two 2" Witness corners on line 33 ft. east and south. 1974

Retied W.C.'s April 16, 1975.

East WITNESS Replaced after milling project, 1989?

Re-tied Aug. 9, 1990

Set P.K.'s. and retied. 7-27-94

Set 20" C.I.M. (33' east and 33' south) 9-94

Tied out Mon. 3665 and removed for Maplewood 4-25-00

Reset Mon. 3665 & MH assembly. 7-11-01

Retied monu's. 4-7-03

RETIED MON. 366E & MON. 366S 10-08-09

Tied out monument 366E for removal during road reconstruction 5-25-10

Reset Mon. 366E; placed a 20 in. C.I.M.

within a cast iron manhole assembly 10-13-10

Tied Mon. 366E 10-14-10

366
EAST & SOUTH

COMPUTED

Checked: 5-11-81

⊠ @ 366E ~ Azm 0°
SOCCER

~ Ho. 164.35 (149°26'50")

~ Hyd (218-25-39)

~ Fire sta (59-00-54)

~ tree (71-36-31)

~ fence (274-28-59)

