

WEST 1/4 COR. SEC. 17-29-22

MONU. NO. 430

Found cast iron monu. flush and
re-tied. Sept. 18, 1974.

Removed cast iron monu. 6-15-90

Placed 20" cast iron 10-25-90

Removed C.I. for Maintenance. 4-92

Set 20" C.I.M. 10-13-92

Retied. 7-8-02

RETIED MONU 8-09-07

Tied monument for removal during road
reconstruction. 8-22-12

Removed "Ramsay County" 20" Cast Iron
monument, found a 5/8 in. solid rod down
26 in. below F/G. Rod matched position
North and South and was 0.04 ft East
of position. Reset existing C.I.M. down
4 in. at its previous position. Left 5/8 in.
rod in place. Placed a cast iron manhole
assembly over C.I.M.; tied 9-6-12

