



PLAT OF SURVEY

DESCRIPTION: Commencing at the meander corner at the Northwest corner of Government Lot 2, Sec. 2-30-22, thence East along the North line of said Government Lot 2 - 350 feet, thence Southeasterly at an angle of 48° 07' to the right 624.65 feet to the point of beginning of land to be described, thence continuing Southeasterly along the same line, a distance of 150.1 feet to a point, thence Southwesterly at an angle of 92° 10' to the right to the shore of Bald Eagle Lake, thence along the shore of Bald Eagle Lake to the line which is 150 feet Northwesterly of and parallel to the most Southerly boundary line of land being described, thence Northeasterly in a straight line parallel to the most Southerly line of land being described to the point of beginning.

Easement: Also an easement for ingress and egress over a strip of land 8 feet wide the center line of which is described as follows; Commencing at the meander corner corner of Government Lot 2, Sec. 2-30-22, thence East along the North line of said Government Lot 2 - 350 feet, thence South 41° 53' East 624.65 feet to a point, thence South 50° 17' West 100 feet to the point of beginning of line to be described, thence North 41° 53' West a distance of 157.7 feet to a point, thence North 33° 17' West a distance of 418 feet to a point, thence North 36° 24' East a distance of 38 feet more or less to the line previously described as South 41° 53' East and there terminating.

Scale 1" = 50'
o indicates Iron.

T. J. Welch, Reg. Surveyor,
739 Summit Ave. St. Paul, Minn.
Tel. 70. 0640. Sept. 1945.

NORTH

MEANDERED ROAD

BALD EAGLE LAKE

Bald Eagle Lake

134
53-84

135
8-9-18