

FROM THE OFFICE OF

CHARLES O. GEORGI COMPANY

2215 West County Road B

Saint Paul, Minnesota 55113

REGISTERED CIVIL ENGINEER AND LAND SURVEYOR

Certificate of Survey

I Hereby Certify that this plat shows a survey made by me of the property described on this plat, and that the corners are correctly placed as shown, and that all locations have been correctly shown.

Surveyed For PART AUTHORITY

Date August 1966

Scale 1" = 200'

By Charles O. Georgi
REGISTERED LAND SURVEYOR

Description:

Eva St. as relocated in 1963

A strip of land 80 feet in width of which the centerline is described as follows

Commencing at the intersection of the centerlines of Fillmore Ave. and old Roberts as dedicated by the plat of Bazille and Roberts' Addition, thence Northeasterly along the centerline of said Fillmore Ave a distance of 813.15 feet to the point of beginning of centerline here in described, thence Southeasterly at right angles a distance of 80 feet to a point of curve, thence Southerly along the curve for a arc distance of 252.75 feet, $\Delta = 10^{\circ}06'36''$ to the right and $R = 1432.40$ feet to end of curve, thence continuing Southerly tangential from said curve a distance of 1023.25 feet to a point on a travelled road known as Plato Blvd. and there terminating.

