

CHARLES O. GEORGI COMPANY

2215 West County Road B

Saint Paul 8, Minnesota

MINNESOTA REGISTERED LAND SURVEYOR



Certificate of Survey

I Hereby Certify that this plat shows a survey made by me of the property described on this plat, and that the corners are correctly placed as shown, and that all locations, encroachments, etc., have been correctly shown. Only block corner offset drill holes in concrete at one foot was placed.
5/68-added NWly parcel data & description.

Surveyed For HOUSING AND REDEVELOPMENT AUTHORITY

Date December 15, 1967

Scale 1" = 50'

By *Charles O. Georgi*
REGISTERED LAND SURVEYOR

Description: (NEly parcel)

All that part of Lot 1, 2, 3, 4, 5, 6, 11, 12, 13 and 14, Block 9, City of St Paul (St. Paul Proper) lying within the following described parcel of Land:

The Northerly 160.6 feet (measured at right angles) of said Block 9 except that part lying Westerly of the following described line;

beginning at a point on the Southerly line of the Northerly 160.6 feet of said Block 9 distant 207.99 feet Westerly of the East line of said Block 9, thence Northerly at right angles to said Southerly line a distance of 160.6 feet to the Northerly line of said Block 9 and there terminating;

except the Easterly 10 feet for widening Cedar Street and except the Northerly 4 feet for widening East 6th Street.

contains 30,824 Sq. Ft., more or less

All in Ramsey County, Minn.

Description: (NWly Parcel)

The Northerly 77 feet of Lots 7 and 8; and that part of the Northerly 77 feet of Lot 6 lying Westerly of the following described line: beginning at a point on the Southerly line of the Northerly 160.6 feet of Block 9 distant 207.99 feet Westerly of the East line of Block 9, thence Northerly at right angles to said Southerly line a distance of 160.6 feet to the Northerly line of Block 9 and there terminating.

except the Northerly 4 feet for widening East 6th Street and except the Westerly 2 feet for widening Wabasha St. All in Block 9, City of St Paul, (St Paul Proper), Ramsey County, Minn.

contains 8,984 Sq. Ft., more or less.

