


Description Westview Industrial Park
 Lot 5, Block 3 Westview Industrial Park

L-5, B-3

That part of the Southeast Quarter (SE 1/4) of the South West Quarter (SW 1/4) of Section 20, Township 28, Range 22, described as follows: - beginning at a point 76.0 feet North and 228.0 feet East of the South West corner of said SE 1/4, SW 1/4, of Section 20, being the Northerly line of Marie Avenue, thence East 6.97 feet to the beginning of a curve to the Northeast, central angle 45° 00', Radius 252.94 feet, thence along the curve a distance of 198.66 feet to the end of the curve, thence North 45° 00' East a distance of 120.0 feet, thence North 41.0 feet thence West 272.0 feet thence South 206.7 feet to the point of beginning, containing 40,254 Square feet or 0.925 acres.

W.H. Carlson
 Registered Surveyor

Scale 1" = 100'
 Jan. 4, 1966



Note: Plat and description prepared from existing data, not surveyed.

