

Port Authority
Riverview Industrial Park

Vault

C.O. Georgi
9/8/72
9/11/72 added exact distances.

Parcel - 5 Ac. lying Southerly of Metro-Meats building face.

All that part of Govt Lot 11 and Govt Lot 12 of Section 5, T28N, R22W,
Ramsey County, Minn. lying within the following described lines:

Commencing at the intersection of the centerline of Plato Ave. and the centerline
of old Robert St., thence NEly at right angles to the centerline of old Robert St. a
distance of 350 feet, thence Easterly by a deflection angle of $19^{\circ}40'11''$ to the right
a distance of 1319.72 feet to a point of Curve, thence NEly along a curve with
 $\Delta = 41^{\circ}42'55''$ to the left and $R = 1432.40$ feet for an arc distance of 1038.72 feet
to a point, being the intersection of the centerline of future Chester St. and
Plato Blvd., thence SEly at right angles to the tangent of said curve 186.77 feet,
thence Southerly by a deflection angle of $51^{\circ}46'20''$ to the right 211.18 feet, thence
Easterly by a deflection angle of $90^{\circ}01'01''$ to the left 40 feet to the point of
beginning of the land herein described, thence continuing Easterly along the
aforesaid line extended a distance of 391.6 feet along the Southerly face of the
concrete block building, thence Southerly at right angles 36.0 feet along the westerly
face of the concrete block building, thence Easterly at right angles 63.14 feet along
the Southerly face of the concrete block building, thence Southerly at right angles 560.86
feet, thence Westerly at right angles 314.02 feet to the Easterly line
of future Chester St., thence Northerly by a deflection angle of $90^{\circ}01'01''$ to the right
156.48 feet to a point of Curve, thence NWly along a curve with
 $\Delta = 34^{\circ}00'$ to the left and $R = 350$ feet for an arc distance of 207.69 feet to
end of curve, thence NWly tangential to said curve 62.39 feet to a point of curve,
thence Northerly along a curve with $\Delta = 34^{\circ}00'$ to the right and $R = 270$ feet
for an arc distance of 160.22 feet to end of curve, thence Northerly tangential
to said curve 41.9 feet to the point of beginning.

Subject to a railway easement over the Easterly 17 feet thereof.
and subject to the projections of the building wall pilasters.

Contains 217,800 Sq. Ft., more or less
5.00 Acres, more or less

For drawing - see attached Certificate of Survey