

DESCRIPTION:
See small certificate attached for description

NOTES:
Part Authority Datum = City Datum of 1912 adj plus 694.1 feet
Thus add 0.48 to get U.S.G.S. Datum.
B.M. 704.40 Top arrow NW cor State St. & Plato Blvd.
B.M. 704.43 Top hyd sw cor plato Blvd. & Frontage Road.
B.M. 704.90 Top hyd 210' North of Plato on W. side of
Frontage Road. (as shown)
M.H. Denotes Man Hole
L.P. Denotes Light Pole
C.B. Denotes catch Basin
P.P. Denotes Power Pole
I.M. Denotes Iron Monument
E. 703.3 Denotes Elevation 703.3
H.D. Denotes Fire Hydrant

All utilities per public record and to accuracy of same
Call N.S.P. and Bell Telephone for any buried cables
prior to digging.
Design Location by T.R.O.A. Engineers
Telephone is 4 feet west of property line along Frontage Rd.
3" Gas is 3 feet west of property line along Frontage Rd.
6" Gas main along west side of State St. 8' west of face of curb.



SITE MAP
SHERATON HOTEL
ST. PAUL, MINNESOTA

SCALE 1" = 30'

Charles O. Georgi Company
Civil Engineering & Land Surveying
2215 W. Co. Rd. B. St. Paul 13, Minn.

March 1970

Survey in accordance with Gauger & Associates
INC.

Now part of
R.L.S. #241

