

SE 14 29 22

FROM THE OFFICE OF

CHARLES O. GEORGI COMPANY

2215 West County Road B

Saint Paul 13, Minnesota

REGISTERED CIVIL ENGINEER AND LAND SURVEYOR

Certificate of Survey

Note:

See attached Certificate
11" x 17 1/2"

I Hereby Certify that this plat shows a survey made by me of the property described on this plat, and that the corners are correctly placed as shown, and that all locations have been correctly shown.

Surveyed For ... W^m Reeves

Date..... January 18, 1965

Scale..... None

By.... Charles O. Georgi

REGISTERED LAND SURVEYOR

Description: (for Minneapolis and St. Paul Suburban Railroad Company Right-of-Way in the SE 1/4 of Section 14 T29N R22W - with recommended revisions)

That part of the SE 1/4 of Section 14, T29N, R22W described as follows: beginning at a point on the North line of the said SE 1/4 of Section 14 distant 1241.94 feet West of the Northeast corner thereof, said point being the intersection point of the Easterly Right-of-Way line of the Minneapolis and St Paul Suburban Railroad Company with the said North line of SE 1/4 of Section 14; thence S 0°0'9" W along the said Easterly right-of-way line a distance of 285.54 feet to the beginning of a curve; thence Southerly along a curve with a radius of 1860.08 feet and a delta angle of 12°05'1/2" to the left for an arc distance of 392.55 feet to the end of curve; thence S 11°56'1/2" E a distance of 694.94 feet to the beginning of a curve; thence Southerly along a curve with a radius of 1482.69 feet and a delta angle of 48°01' to the right for an arc distance of 1242.57 feet to the end of Curve; thence S 36°04'1/2" W a distance of 83.6 feet more or less to the point of intersection of said Easterly right-of-way line with the Northerly right-of-way line of Larpenteur Ave, being 33 feet North of the South line of said Section 14; thence Westerly on the said Northerly right-of-way line of Larpenteur Ave. to its point of intersection with the Westerly right-of-way line of said Railroad Company, being a line parallel and distant 100 feet Westerly, measured at right angles, to aforesaid Easterly right-of-way line; thence Northerly on said parallel westerly right-of-way along tangents and curves to its intersection point with the West line of the NE 1/4 of the SE 1/4 of said Section 14; said intersection point being 637.10 feet South of the North line of the SE 1/4 of said Section 14; thence Northerly on the West line of the NE 1/4 of the SE 1/4 of said Section 14 a distance of 128.18 feet to the point where said Westerly right-of-way line is distant 80 feet Westerly of said Easterly right-of-way line; thence Northerly on the Westerly right-of-way line parallel to and distant 80 feet Westerly, measured at right angles, to the said Easterly right-of-way line to the point of intersection with the North line of the SE 1/4 of said Section 14; thence East on the North line of the SE 1/4 of said Section 14 a distance of 80 feet to the point of beginning.