

**Certificate  
of Survey**

Job Number: 3397  
Surveyed For: Frank Frattalone  
Date: 4/15/88  
Scale: -----

NE 4 29 22

From the office of

**GEORGI-SCHMIDT & ASSOC. INC.**

3092 No. Lexington Ave., Roseville, Mn. 55113

LAND SURVEYING

483-4408

I hereby certify that this plat shows a survey made by me of the property described on this plat, and that the corners are correctly placed as shown, that this survey, plan or report was prepared by me, or under my direct supervision; and that I am a duly registered Land Surveyor under the Laws of the State of Minnesota.

by REGISTERED LAND SURVEYOR  
Mn. Registration No. 10459

**DESCRIPTION:**

A roadway and drainage easement over, under and across those parts of the Southwest quarter of the Northeast quarter of Section 4, Township 29 North, Range 22 West described as follows:

A 60 foot roadway easement lying 30 feet on either side of the following described lines:

Commencing at the East quarter corner of said Section 4; thence West (assumed bearing) along the South line of said Northeast quarter a distance of 1326.69 feet to the Southeast corner of said Southwest quarter of Northeast quarter as established by a previously found iron pipe and the point of beginning of the center line of said 60 foot roadway easement; thence continuing West 260.24 feet; thence Northwesterly 379.53 feet along a tangential curve to the right, radius of 304.40 feet, delta angle of 71 degrees 26 minutes 16 seconds to a point of reverse curve; thence continuing Northwesterly along a tangential curve to the left 320.80 feet, radius of 700 feet, delta angle of 26 degrees 15 minutes 28 seconds to a point of reverse curve; thence continuing Northwesterly along a tangential curve to the right 216.69 feet, radius of 500 feet, delta angle of 24 degrees 49 minutes 52 seconds to a point of reverse curve; thence continuing Northwesterly along a tangential curve to the left 163.9 feet, radius of 600 feet, delta angle of 15 degrees 39 minutes 15 seconds to a point herein after referred to as point "A" and there terminating.

A 20 foot drainage easement lying Southerly of the following described lines:

Beginning at the above described point "A"; thence South 61 degrees 16 minutes 08 seconds West 190.66 feet along a non-tangential line; thence South 89 degrees 16 minutes 08 seconds West 40 feet to a point herein after referred to as point "B" and there terminating.

And a drainage easement lying within the following described lines: Beginning at the above described point "B"; thence South 89 degrees 16 minutes 08 seconds West a distance of 160 feet to the West line of said Southwest quarter of Northeast quarter; thence 80 degrees 43 minutes 52 seconds East 470 feet along said West line; thence North 79 degrees 16 minutes 08 seconds East 350 feet; thence North 30 degrees 43 minutes 52 seconds West 324 feet; thence North 10 degrees 43 minutes 52 seconds West 130.61 feet to the point of beginning.

Ramsey County, Minnesota