

**Certificate
of Survey**

From the office of
GEORGI-SCHMIDT & ASSOC. INC.
3092 No. Lexington Ave., Roseville, Mn. 55113
LAND SURVEYING
483-4408

I Hereby Certify that this plat shows a survey made by me of the property described on this plat, and that the corners are correctly placed as shown, and that all locations have been correctly shown.

Job Number: 423

Surveyed For Richard Carrier

Date August 3, 1979

Scale 1" = 50'

By Donald W. Schmidt
REGISTERED LAND SURVEYOR

Description:

Commencing at a point 616 feet North of the SW corner of the SW 1/4 of Section 2, T 29 N, R 23 W; running thence North along the West line of said Section 2 133.8 feet ± to centerline of County Road C; running thence East along said centerline of said County Road C 160 feet; running thence South 133.8 feet ± to the NE corner of land conveyed to George J. Reiling by deed records in Book 1020 of deeds on page 153 thereof; running thence West along North line of said of said land of said George J. Reiling 160 feet ± to the said West line of said Section 2; being the said point of beginning; subject to all easements taken for highway purposes.

***Book 1020, Page 153**

Commencing at a point 496 feet North of the SW corner of Section 2, T 29 N, R 23 W, thence North 120 feet; thence East 160 feet; thence South 120 feet; thence West to the point of beginning.

Surveyors Note.

The centerline of County Road C according to Reiling Park is 745 feet North of South line of Section. Old county maps indicate 749.8 along Lexington Ave. Previous surveys used 745 and 33 feet off for street. This survey locates County Road C and existing iron in accordance with previous surveys.

- o Denotes Iron Pipe Monument set.
- Denotes Iron Monument found.

