

FROM THE OFFICE OF

CHARLES O. GEORGI COMPANY

2215 West County Road B

Saint Paul, Minnesota 55113

REGISTERED CIVIL ENGINEER AND LAND SURVEYOR



I Hereby Certify that this plat shows a survey made by me of the property described on this plat, and that the corners are correctly placed as shown, and that all locations have been correctly shown.

Surveyed For *Robert C. Witt*

Date *November 1975*

Scale *1" = 50'*

By *Charles O. Georgi*
REGISTERED LAND SURVEYOR

Description:

All that part of the SW¹/₄ of Section 32, T30N, R22W described as follows:

Commencing at a point on the East line of said SW¹/₄ distant 1133.25 Feet North of the Southeast corner of said SW¹/₄, thence West (assumed bearing) 835 feet parallel to the South line of said SW¹/₄, thence S 38°32'W 323.1 Feet to the point of beginning of the parcel of land herein described, thence South 125 Feet to point distant 1037.8 feet West of the said East line of SW¹/₄ of Section 32, and 755.5 Feet North of the South line of said SW¹/₄ of Section 32, thence West 313.3 Feet, more or less, parallel to the said South line of SW¹/₄ of Section 32 to the centerline of Centerville Road, thence N 38°03'45"E 245.00 Feet along the centerline of Centerville Road, thence S 67°17'50"E 175.88 Feet, more or less, to the point of beginning.

