

FROM THE OFFICE OF

**CHARLES O. GEORGI COMPANY**

2215 West County Road B

Saint Paul 13, Minnesota

REGISTERED CIVIL ENGINEER AND LAND SURVEYOR

**Certificate  
of Survey**

I Hereby Certify that this plat shows a survey made by me of the property described on this plat, and that the corners are correctly placed as shown, and that all locations have been correctly shown.

Surveyed For P. OLSON

Date March 1961

Scale 1"=100'

By Charles O. Georgi  
REGISTERED LAND SURVEYOR

**Description:**

All that part of Government Lot 1, Section 8, T29N, R21W described as follows:  
Commencing at the Northeast corner of Government Lot 1 in said Section 8, Thence West along the North line of said Government Lot 1 a distance of 1395.13 feet to the point of beginning, thence Southeasterly by a deflection angle of 109°10' to the left a distance of 220.43 along the Easterly line of Olson Lake Road, thence Easterly by a deflection angle of 50°58' to the left a distance of 397.95 feet to a point on the shore line of Olson Lake, thence Northerly by a deflection angle of 92°26' to the left a distance of 59.07 feet along the shore line of Olson Lake, thence Northwesterly by a deflection angle of 59°44' to the left a distance of 387.96 feet to a point on the North line of said Government Lot 1, thence Westerly along the North line of said Government Lot 1 a distance of 203.43 feet to the point of beginning, subject to DeMontreville Road on and across the North 33 feet thereof.

