

FROM THE OFFICE OF

# CHARLES O. GEORGI COMPANY

2215 West County Road B

Saint Paul 8, Minnesota

REGISTERED CIVIL ENGINEER AND LAND SURVEYOR

## Certificate of Survey

I Hereby Certify that this plat shows a building location survey made by me on the property described on this plat, and that all locations, have been correctly shown.

Date.....December 22, 1959

Scale 1" = 100'

By *Charles O. Georgi*  
REGISTERED LAND SURVEYOR

For: GENE GAUTHIER.

*P.H. Olson*

### Description:

All that part of Government Lot 2, Section 8, T29N, R21W, 4th Meridian, which is bounded by the following described line:

From the Meander corner on the Southwesterly shore of Olson Lake distant 145.2 feet Northerly of the East Quarter corner of said Section 8; run Northwesterly at an angle of 53°11' with the East line of said Section for a distance of 378.5 feet; thence deflect to the left at an angle of 2°43' and continue Northwesterly for a distance of 341.3 feet; thence deflect to the right at an angle of 33°26' and run Northwesterly for a distance of 35 feet to the point of beginning; thence continue Northwesterly along the last described course for a distance of 215 feet, thence deflect to the left at an angle of 90° and run Southwesterly for a distance of 215.6 feet; thence deflect to the left at an angle of 91°05' and run Southeasterly for 108.5 feet, thence deflect to the right at an angle of 1°09' and run Southeasterly for a distance of 106.5 feet; thence run North-easterly 215.7 feet to the point of beginning and there terminating, containing 1.06 Acres more or less, according to the United States Government Survey thereof.

