

FROM THE OFFICE OF

CHARLES O. GEORGI COMPANY

2215 West County Road B

Saint Paul 13, Minnesota

REGISTERED CIVIL ENGINEER AND LAND SURVEYOR



Certificate of Survey

I Hereby Certify that this plat shows a survey made by me of the property described on this plat, and that the corners are correctly placed as shown, and that all locations have been correctly shown. *Property Survey June 1958 & June 1961
House location June 1963*

Surveyed For Mr. Brown

Date June 1963

Scale 1" = 100'

By Charles O. Georgi
REGISTERED LAND SURVEYOR

Description:

Subject to Demontreville Road and Combs Road, all that part of Govt Lot 1 of Section 8, T29N, R21W, Washington County, Minnesota described as follows: beginning at a point on the North line of said Govt Lot 1 distant 841.7 feet west of the Northeast corner of said Section 8, thence continuing west on aforesaid North line extended a distance of 125.0 feet to a point, thence southeasterly by a deflection angle of 108°00' to the left a distance of 261.0 feet to a point, thence northeasterly along the shore of Olson Lake by a deflection angle of 110°28' to the left a distance of 126.9 feet to a point, thence northwesterly by a deflection angle of 69°32' to the left a distance of 178.0 feet to the point of beginning.

ALSO all that part of Govt Lot 1 of Section 8, T29N, R21W, Washington County, Minnesota described as follows: beginning at a point on the North line of said Govt Lot 1 distant 741.7 feet west of the Northeast corner of said Section 8, thence continuing west on the aforesaid North line extended a distance of 100.0 feet, thence southeasterly by a deflection angle of 108°00' to the left a distance of 178.0 feet, thence northeasterly along the shore line of Olson Lake by a deflection angle of 110°28' to the left a distance of 100.0 feet, thence northwesterly by a deflection angle of 68°48'30" to the left a distance of 112.09 feet to the point of beginning.

