

COUNTY OF RAMSEY
OFFICE OF COUNTY AUDITOR
ROAD RECORD

W. P. A. PROJ. 8546
O. P. 65-1-71.2668

NAME Koehler Road
ROAD NO. 27
FROM McMenemy Street
TO Centerville Road

REMARKS:

Field notes of Survey of a County Road.
Road from Plat Book
Pages 21 and 22

Project File #424

Field notes of a survey for county road from Rice Lake road by Feston's Farm, thence to Morrisettes and thence to an intersection with the Little Canada Road on the premises of A. Labonne, Sr., Commencing at a stake center Rice Lake Road (Wit. B. O. 12" Diam. Bearing north 77 deg. 45 min. west 63 links) thence---

County Road from Rice Lake Road to White Bear Road

Sta.	Chains	Objects to which Brgs. are taken	Wit. Trees	Bearings	Remarks
2	20.20	Stake	B.O.S. 12 $\frac{1}{4}$ deg. west 89 Li.	S. 63 deg. 45 min. E.	
3	9.53	B.O. Tree		S. 80 deg. 15 min. E.	
4	4.63	B.O. Tree		S. 77 deg. 15 min. E.	
5	11.52	B.O. Tree		S. 86 deg. E.	
6	16.10	Stake	B.O.S. 17 $\frac{1}{2}$ deg. east 83 Li.	S. 74 deg. 30 min. E.	Vadnais Lake
7	10.00	Stake		S. 63 deg. E.	
8	4.50	Stake		S. 59 deg. 30 min. E.	
9	6.80	Stake	B.O.S. 70 $\frac{1}{2}$ deg. west 76 Li.	S. 35 deg. 45 min. E.	
10	13.00	Stake	B.O.S. 88 $\frac{1}{2}$ deg. east 72 Li.	S. 33 deg. 30 min. E.	
11	3.23	Stake	W.O.N. 53 $\frac{1}{4}$ deg. east 95 Li.	S. 5 deg. 30 min. W.	
12	20.00	Stake		South	to Southwest corner 29-30-22) Northwest quarter of Southwest) quarter)
13	40.00	Stake	B.O.N. 62 deg. East 62 Li.	East	
14	5.42	Stake		S. 9 deg. 15 min. E.	
15	4.90	Trees and Stakes		S. 36 deg. 30 min. E.	30 ft. to right of Labonne's) Lake)
16	4.14	Stake		S. 45 deg. E.	
17	5.53	Stake		S. 67 deg. 15 min. E.	
18	6.67	Stake		S. 85 deg. E.	
19	11.90			S. 79 deg. 15 min. E.	to Little Canada Rd. Course

James A. Case, Co. Surveyor)
Chris Beebe) Viewers S. 33 $\frac{1}{2}$ deg. west Course of Rice Lake Road North and South
Batteso Forohen)

Joseph Labonne, Sr.) Chainman Length of Road 2.47 miles
Henry Loverin)
J. Labonne, Sr.) Axeman

Road Plat Book #1
Pages 21 and 22