



PROPOSED BRIDGE RAILING FOR RAMSEY COUNTY, MINN.
 OFFICE OF COUNTY SURVEYOR
 SCALE NOTED - JULY 2, 1948
 TWO (2) RAILS THUS REQUIRED - ONE (1) ON EACH SIDE OF BRIDGE
 LOCATION OF BRIDGE - ON KELLER PARKWAY OVER CANAL
 BETWEEN GERVAIS AND KOHLMAN'S LAKES.

Note: - Fill 6"x1'-4" Rectangular Holes in Concrete Curb Blocks with 2000* concrete and set posts therein. Post and Rail Sizes shown. Type of Mesh shown. Mesh to be hot dipped galvanized. Paint Posts and Rails two (2) coats aluminum paint.