



STATEMENT OF ESTIMATED QUANTITIES			
Item Number	ltem	Unit	Estimated Quantity 100% S.A.P. 62-657-02
	Mobilization	L.S.	1
	Mill Bituminous Surface (1 1/2")	S.Y.	17,107
	Type MVWE35035B (1 1/2") Wearing Course Mixture	Ton	1,653
	Bituminous Material for Tack Coat	Gal.	855
	Adjust Valve Box	Each	3
	Adjust Frame & Ring Casting	Each	4
	Construct Survey Control Structure	Each	1
	Traffic Control	L.S.	1
	Pavement Message (Railroad Emblem) Poly Preform	Each	2
	24" Stop Line White - Poly Preform	L.F.	24
	24" Yellow Hashmark - Epoxy	L.F.	75
	12" Solid Line White (Survey Marker) - Epoxy	L.F.	20
· · · · · · · · · · · · · · · · · · ·	Zebra Crosswalk White - Epoxy	S.F.	290

MN/DOT STANDARD PLATES		
PLATE NO.	DESCRIPTION	
80001	STANDARD BARRICADES	

BASIS FOR ESTIMATED QUANTITIES

1. 115 LBS. / SQUARE YARDS / INCH OF BITUMINOUS

2. .05 GALLONS OF BITUMINOUS TACK COAT /SQUARE YARD OF PAVEMENT / LIFTS

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY
DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL
ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA

NAME

NAME

MN REG NO. 21864 DATE 4/19/06

MCMENEMY ROA

ESTIMATED QUANTITIES

S.A.P. 62-657-006 SHEET 2 of 6 SHEETS

Design on Ispw1(H:)/Land Projects 3/05-OLAY/dwg/MCMENEMY ESTIMATED QUANTITIES

28-248







