



16d Common Nails

2x12-9 1/2" Long

Pole 6" Diam. Top

2x12-8'6" Long

2x12-6'4" Long

Dots indicate 16d Common Nails - Clinch at back ends.

1/2" M. Bolts - 11" Long under heads  
Cut Washers. Square Heads and Nuts.

BILL OF MATERIAL				
Number Required	Item	Size	Length	Notes
1	Cedar Pole	6" Diam. Top	14'-0"	Penta Treated
2	Sign Boards	2"x12"	10'-0"	S4S #1 Fir
1	Braces	2"x6"	12'-0"	S4S #1 Fir
8	Machine Bolts	1/2" Diam.	11" Under Head	W.I.
16	Cut Washers	For 1/2" Diam. M Bolts		Steel
1/2 Gallon	Paint			Pittsburgh Sun Proof Outside White
1 Quart	Paint			" " " " Black
1 1/2 Pounds	Nails	16d		

Note: See Data under "Notes" in above Bill of Material.  
Build Unit as shown on this sheet. Poles will be buried 4'-0" into ground and securely packed in. Poles will not be painted but all other lumber will be primed and receive two coats of Pittsburgh Sun Proof Outside White Paint.  
After White Paint has dried, paint the letters as shown with black paint.

DETAILS OF SIGN INSTALLATION  
FOR  
PICNIC AREAS IN RAMSEY COUNTY.  
SCALE 1/2"=1'-0"  
AUGUST 1952  
R. B. BARNER  
COUNTY ENGINEER